

Automatic Pallet Stretch Wrapper

Model:

PP-1621AL

Fully automatic stretch machine with cut, clamp and swipe.

Series Features

- 300% Power pre-stretch
- 4,400lb load capacity
- Photo Eye
- "Easy Thread Design"
- New digital control panel with all standard features
- Fully Automatic - Cut, Clamp and Swipe

Film Saver!

With a 300% powered pre-stretch system, a standard 20"x 5,000 ft machine film roll will apply 20,000 ft of film to the load providing a tremendous film yield and a quick ROI through film cost savings.

Time Saver!

- Complete wrap cycle takes 1 minute from start to finish
- Fully Automatic with remote control
- Improve productivity by keeping the operator on the forklift
- Capable of wrapping 30-40 loads per hour
- Forklift portable (front or rear)
- No scheduled preventative maintenance
- Save two minutes of forklift driver labor per load



Preferred Pack®

The New Industry Standard for Quality and Reliability

Line of Equipment by **EXCEL** PACKAGING

User-Friendly Control Panel



- OMRON 6" Color Touch-Screen
- HMI Mitsubishi PLC Control
- On/Off Switch
- Top Wrap Count
- Bottom Wrap Count
- Start/Stop
- Manual/Automatic
- Film Tension Control
- Turntable Speed
- Film Carriage Speed
- Emergency Stop Switch

Cut & Swipe System



Pneumatic Clamping



- Patented double knurled roller pre-stretch system with 300% powered pre-stretch. Easy thread design with safety door.
- Heavy duty chain drive on turntable with 14 sets of double roller turntable supports.
- No maintenance or lubrication required.



Comes with two remote controls.

Technical Specifications:

Production Rate:	30-40 Loads Per Hour
Power Requirements:	115 Volts, 1 Phase, 15 Amp
Air Required:	1 CFM @ 60 psi
Maximum Load Size:	48" L x 40" W x 83" H
Maximum Load:	4,400 lbs.
Turntable:	65" diameter - 3/8" Diamond Plate
Turntable Drive:	1 HP AC variable speed 0-15 rpm
Turntable Drive Method:	Heavy Duty Chain ANSI #60
Turntable Support:	Heavy Duty Delrin Roller Assembly
Film Delivery System:	Patented double knurled roller with "Easy Thread Design" to stretch film 300%
Machine Dimensions:	113" L x 81" W x 96" H
Carriage Elevator:	Variable speed 1/2 HP- drive belt
Controls:	Mitsubishi PLC control
Photo Eye:	Will seek height of pallet load
Forklift Portable:	Yes
Home Position:	Turntable will automatically return to home position
C.E. Approval:	Exceeds OSHA Safety Standards
Warranty:	3 Year Limited Warranty
Film Capacity:	All Commercial 20" Wide Stretch Film
Shipping Weight:	2,000 lbs.

Optional Features:

- 71" diameter turntable
- Tower extension to 95" or 106"
- Loading ramp
- Weight scale packages
- Additional remote controls
- Alarm sensor for film clamp protection

Dimensions:

